

THE PHARMACEUTICAL CORPORATION (IM) KERALA LTD.
THRISSUR

TENDER DOCUMENT

Name of work: Mezzanine Floor Additional Works – Structural Support for
Monorail Hoist at Oushadhi Kuttanellur.

Proforma

1. Name of work : Mezzanine Floor additional works –
Structural Support for Monorail Hoist at
Oushadhi Kuttanellur.
2. Tender Qualification : As per clause 4 in General Conditions
3. Estimated amount : Rs. 2,70,000/-
4. Name of Tenderer :
5. Address of the Tenderer :
6. Telephone No. of the
Tenderer :
7. Sale date of tender document : 18.09.2019
8. Last date of receipt of tender document : 25.09.2019 at 3.00 pm
9. Date of opening of tender document : 25.09.2019 at 3.30 pm
10. Details of EMD : Rs. 6800/-
11. Time of completion : One Month
12. Period of maintenance : 12 Months from the date of
Completion

Signature of Tenderer

GENERAL CONDITION

1. The tender shall be submitted in the document purchased from the office or down loaded from the website.
2. Last date of submission of tender is 25.09.2019 at 3.00 pm and tender will be opened on the same day 3.30pm
3. No tender will be accepted after the stipulated time and date
4. The bidder should have valid GST registration, PAN, ESI and PF Registration. The bidder should have appropriate class registration in PWD/CPWD/Govt. undertakings.
Similar work for the purpose of eligibility shall be construction of a pre-fabricated building and execution of associated civil works.
5. The cost of tender document is Rs. 605/- (Inclusive of GST @12%). Those who down load tender document should remit the cost of document along the tender. Cost of tender document can be remitted in the form of DD drawn in favour of Managing Director, Oushadhi, payable at Thrissur or by cash. In case tender cost is remitted by cash receipt shall be submitted along with the tender.
6. The cover containing the tender should be super scribed with words “Mezzanine Floor additional works –Structural Support for Monorail Hoist at Oushadhi Kuttanellur”
7. The tender should be submitted along with EMD of Rs. 6800/-. EMD can be remitted in the form of DD drawn in favour of Managing Director, Oushadhi payable at Thrissur or by cash. In case EMD is remitted by cash, cash receipt shall be submitted along with the tender. The EMD of unsuccessful tenderer will be returned without any interest after 30 days from the date of finalization of tender.
8. The entire work should be completed within **one month** from the date of receipt of firm order.
9. An amount equal to 5% of the quoted amount of work should be remitted by the successful tenderer towards the security deposit which will be released only after 12 months from the date of completion of work. If the successful tenderer fails to remit the Security Deposit and execute an agreement in the prescribed format in stamp paper of required value within 7 days from the date of receipt of our

letter of acceptance, the tender is liable to be rejected and the E.M.D remitted shall be confiscated.

10. The rate quoted should be inclusive of all taxes and it should be firm without any escalation till the orders in completely executed.
11. The payment in full will be released after 30 days from the date of submission of final bill after successful completion of the work
12. Time being the essence of the contract, the time of completion stipulated should be strictly adhered to.
13. If the tenderer fails to satisfactorily complete the work with in the period stipulated in the tender, Corporation may at their option either
 - (1) recover from the tenderer liquidated damages at the rate of 2.5% of the contract value, for every week or part there of delay subject to a maximum of 10% of the total executed value.
 - (2) cancel the order wholly or partially and complete it directly or reassign it to other agency at the risk and cost of the tenderer.
14. The tenderer shall visit the work site prior to the submission of the tender if required
15. The tender shall be kept open for a period of one month from the date of opening for acceptance
16. Managing Director reserves unquailed right to accept or reject any or all tender or invite fresh tender or recheck any of the above conditions without assigning any reason whatsoever. The decision of the Managing Director will be final and binding on all.

Signature of Tenderer

THE PHARMACETUICAL CORPORATION (IM) KERALA LTD. THRISSUR

Name of work : Mezzanine Floor Additional Works – Structural Support for Monorail Hoist at Oushadhi Kuttanellur

Sl. No.	Item Description	Quantity	Units	Total Amount In	Total Amount In Words
1.01	Structural steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying two coats of Synthetic enamel paint over two coats of anti corrosive Yellow zincchromate primer including cost and conveyance of all materials, labour charges, lead, lift etc. complete as directed by Engineer- in-Charge at all levels.	2608.000	kg		
1.02	Providing and fixing M.S round holding down bolts with nuts and washer plate including two coats of approved make and colour synthetic enamel paint over two coats of approved make yellow zinc chromate primer, including cost and conveyance of all materials, labour charges,lead,lift etc complete as directed by Engineer-in-Charge	53.000	kg		
1.03	Drilling hole of 20mm diameter and fixing HILTI HIT-V or equivalent threaded rod (Mild Steel-Galvanized) of 16mm diameter using epoxy based heavy duty pre-defined ratio 5:1 injection adhesive HILTI HIT-HY 200 or equivalent in concrete in dry conditions. Embedment depth shall be taken as per the direction of Structural consultant. The adhesive system should be made of two soft foils consisting of resin and hardener foil pack. The installation and the setting instructions should be strictly followed as per the manufacturers recommendations. The system should be fire rated. Rate shall include for all charges and preparation of surface, cleaning the hole with blow-out pump & brush, staging, scaffolding and working platform, application of necessary chemical / foil including rod/bolt ,nut etc as per manufactures specification with necessary tools and equipments, water and power, removal of debris from the site component etc complete, as directed by Engineer-in-charge.	42.000	Nos		
Total in Figures					
Quoted Rate in Words					

Signature of Tenderer