

THE PHARMACEUTICAL CORPORATION (I.M) KERALA LTD.

Name Of Work:- Truss roof Works at Oushadhi Panchakarma Hospital ,Thrissur

BOQ

SI No.	Description of work	Quantity	Unit	Rate in figures & words		Amount Rs.
				In Figures Rs.	In Words	
1	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.35 mm thick of approved make(Jindal, Tata, Jsw) and fixing with GI self drilling /self tapping screws with fastener and EPDM washers etc to the Steel work in built up tubular 16guage of approved make (R.k.s, appolo) round, square or rectangular hollow tubes etc , including cutting, welding, hoisting,boltingg, fixing in position and applying a priming coat of approved steel primer, two coat of synthetic enamel paint of approved shade including fixing ridge (Plain sheet 0.35mm thick) , Euro guard rain water gutter and PVC drain pipe as required as per the specified drawing and direction of Engineer in charge.					
	Post - 3 inch dia Truss pipe - 3x1 1/2 inch Purlin pipe- 1 1/4 inch square Grill pipe - 3/4 inch square					
A	<u>Gable roof with grill (cantilever type)</u> with 1 inch round stainless steel pipe 304 grade, as cantilever support at roof slope end. 2 nos Gable roof with area 70 Sqfeet	140	Sqfeet			
B	<u>Lean to roof(shade roof)</u>	280	Sqfeet			
C	<u>Gable roof</u>	1200	Sqfeet			
D	<u>Lean to roof</u> (cantilever type) with 1 inch round stainless steel pipe 304 grade, as cantilever beam (3 nos)	480	Sqfeet			
	Total amount					
	Gst 18%					
	Grand total					

Signature of tenderer