

THE PHARMACEUTICAL CORPORATION (I.M) KERALA LTD.

Name Of Work:-Laying of new Interlock tiles, dismantling and relaying of existing interlock tiles between Hospital block & SMPB block at Oushadhi Panchakarma Hospital,Thrissur

BOQ

Sl No	Description of work	Quantity	Unit	Rate in figures & words		Amount Rs.
				In Figures Rs.	In Words	
1	Earth cutting by mechanical means /manual means over areas including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m; disposed earth to be levelled and neatly dressed, as directed by the Engineer- in-Charge	1850	Sqfeet			
2	Filling available excavated earth in areas etc. in layers not exceeding 20cm in depth,consolidating each deposited layer by ramming and watering,lead upto 50m and lift upto 1.5m including cost and conveyance of all materials,labour charges, etc complete at all levels as directed by the Engineer-in-Charge	1200	Sqfeet			
3	Providing and laying factory made Cement Concrete paver tiles of required strength,thickness & size/ shape, laid in required colour & pattern over 50mm thick compacted bed of 6mm aggregate laying through vibratory compaction by using plate vibrator, filling the joints with sand and finishing the edge with cement concrete as per direction of Engineer-in-Charge. Paving tiles of 15" x 10" size and 60mm thick, cement concrete block of M-35 grade with approved colour, design& pattern.	1850	Sqfeet			
4	Re-laying of the existing Paver block after providing required earth slope. The work includes removing of the existing paver block and relaying it over 20cm compacted bed of quarry waste and 50mm thick compacted bed of 6mm aggregate laying through vibratory compaction by using plate vibrator, filling the joints with sand and finishing the edge with cement concrete as per direction of Engineer-in-Charge.	1200	Sqfeet			
	Total amount					
	Gst 18%					
	Grand total					
						Signature of tenderer